CITY OF VALLEJO

DEPARTMENT OF PUBLIC WORKS
Engineering Division

555 SANTA CLARA STREET P.O. BOX 3068 VALLEJO CALIFORNIA 94590-5934 707-648-4315
Web Site: www.ci.vallejo.ca.us/ FAX 707-648-4691

March 3, 2010

SUBJECT: **ADDENDUM NO. 3**
Vallejo Station Parking Structure Phase A
(File Number 9866.14.02)

To Prospective Bidders:

The following are changes to the contract specifications and plans for the above referenced project:

This addendum is hereby made a part of the contract documents to the same extent as if they were originally included therein. Receipt of this addendum shall be acknowledged with the bid for Vallejo Station Parking Structure Phase A.

GENERAL NOTICE

The cut off time for submission of bid questions is 5:00 P.M. (Pacific Time) on Tuesday, March 9, 2010. Any questions received after this time will not be responded to. Responses to inquiries will be posted in the city website (http://www.ci.vallejo.ca.us/GovSite/default.asp?serviceID1=133) on Thursday, March 11, 2010.

SPECIFICATIONS: VOLUME A

1. Reference: **COVER SHEET**, Bid Opening Date

   Strike through the following: ~~March 11, 2010~~

   Replace with the following: **March 18, 2010**

2. Reference: **NOTICE TO CONTRACTORS**, page 1

   Remove following paragraph:

~~NOTICE IS HEREBY GIVEN THAT SEALED BIDS will be received at the office of the City Clerk, third floor, City Hall, Vallejo, California, during the business hours of 8:00 AM through 5:00 PM, Monday through Friday, holidays excepted, until the time of **2:00 p.m. on March 11, 2010,** at which time they will be publicly opened and read aloud in the City Council's Chamber of said City Hall for~~

Replace with the following:

NOTICE IS HEREBY GIVEN THAT SEALED BIDS will be received at the office of the City Clerk, third floor, City Hall, Vallejo, California, during the business hours of 8:00 AM through 5:00 PM, Monday through Friday, holidays excepted, until the time of **2:00 p.m. on March 18, 2010,** at which time they will be publicly opened and read aloud in the City Council's Chamber of said City Hall for

3. Reference: **NOTES (PACKAGE #2)**, page 25

Remove the following paragraphs:

~~All ESTIMATED QUANTITIES are approximate …~~

~~Item 41 Mobilization - …~~

~~Item 42 Remove topsoil, landscaping, asphalt and concrete - …~~

~~Item 43 Remove miscellaneous items - …~~

~~Item 61 Irrigation System - …~~

~~Item 76 Miscellaneous Items - …~~

Replace with the attached note:

See Volume B, Section 01220 Unit Prices for Package #2 unit prices.

SPECIFICATIONS: VOLUME B

4. Reference: **TABLE OF CONTENTS**, Division 1 – General Requirements, page 00010-1

Add	01220	Unit Prices

5. Reference: **TABLE OF CONTENTS,** Division 1 – General Requirements, page 00010-1

Delete	01230	Alternates.

6. Reference **SECTION 01100 SUMMARY,** Part 1.01 Summary, Paragraph B, page 01100-1

   Replace paragraph B to read as follows:

   B. Description: The Project is comprised of two below-grade parking levels and one at-grade ground level parking. The total number of parking spaces is approximately *750* with a total square footage of approximately *277,000* gsf.

7. Reference: **SECTION 01220 UNIT PRICES**, page 01220-1

   Add attached Section 01220 Unit Prices

8. Reference: **SECTION 01230 ALTERNATES,** page 01230-1

   Delete Section 01230 Alternates

   This section is not required since the bid will be awarded based on the Total Bid of both Schedule "A" and "B."

9. Reference: **SECTION 01500 TEMPORARY FACILITIES AND CONTROLS**, Part 1.03, page 01500-2

   Replace Part 1.03 with the following:

   1.03 CITY CONSTRUCTION MANAGER'S OFFICE

   A. The Contractor shall at its own expense, furnish a temporary City Construction Manager's office with utilities as noted herein. The office shall be installed and operational one week prior to the Notice to Proceed, before the Contractor starts work at the project site, in a location as directed by the Engineer. Unless the Contractor is directed by the Engineer to remove the office at an earlier date, the office shall be disconnected from the utilities and removed from the site no less than thirty days after the Final Relief of Maintenance has been issued by the Engineer. At such time, the office (except in the case of a rental building) and the office furnishings, shall be removed from site by the Contractor as his property and the area returned to its original condition, except for Category B items stated below which will become the property of the City upon acceptance of the project by the City Council.

   B. The office shall be insulated and of weather tight construction. It shall be equivalent to a mobile trailer having an area of at least 1,440 square feet

(24' x 60'), including internal restroom. The office shall be rigidly mounted and level. Stairs with a landing at floor level and handrails shall be provided for two entrance doors, each complete with deadbolt and or external padlock and four keys.

C. Each window shall be protected with minimum one-half (1/2) inch square security bars spaced at two (2) inch centers.

D. The office shall have four office rooms, a central conference and document storage room plus an internal restroom. There shall be at least one operable screened window per office room. Each room shall be adequately lighted, heated, ventilated, and air-conditioned. HVAC equipment shall be capable of maintaining a 70-degree temperature within the building. At least six air changes per hours shall be provided in all rooms except the toilet room, which shall have twelve air changes per hour.

E. The Contractor shall provide, at its cost, electrical service to the office, including an adequate disconnect switch, and an automatic circuit breaker panel located on the inside of the office. At least one duplex 115-volt electrical receptacle shall be installed on the wall of each room with a maximum spacing between receptacles not to exceed eight feet.

F. Provide fluorescent type lights inside. At least 70 foot-candles of initial uniform lighting at desk level shall be provided in all rooms except the toilet room, which may have 30 foot-candles. Provide an outside light near each entrance door.

G. The Contractor shall arrange, at its cost, with the local utility to provide temporary telephone service at a mutually agreeable location in the Construction Manager's office. The telephone shall provide for four (4) separate lines or extensions and four (4) voice mailboxes.

H. The Contractor shall provide water connection to the toilet room. The toilet room shall contain a flush-type water closet, a lavatory sink with hot and cold water, a mirror, toilet paper dispenser, paper towel dispenser, coat hook, shelf and waste receptacle.

I. A holding tank or similar device shall be installed and connected for sanitary sewage. The Contractor shall pump the holding tank on a weekly basis or as necessary during the duration of the job.

J. The Contractor shall provide a water chiller with hot and chilled water service. The Contractor shall provide bottled water service with two to four 5-gallon bottles each month.

K. The Contractor shall be responsible for paying for the monthly electric power and telephone service.

L. Exterior of the building shall be painted and the completed appearance of the building shall be neat and presentable. Building shall carry a sign bearing the legend in letters approximately 4 inches high:

"CITY OF VALLEJO"
"VALLEJO STATION PARKING STRUCTURE PHASE A"

M. The Contractor shall maintain the field office and its appurtenances in good repair and acceptable appearance, and shall provide cleaning services on a weekly basis and constant maintenance of paper towels, paper cups, soap, toilet paper and other expendables as necessary.

N. The following furniture, furnishings, and equipment shall be provided and maintained for the duration of the contract for the exclusive use of the Engineer:

<u>CATEGORY A: Furniture, Furnishings, and Equipment:</u>

The following furniture, furnishings, and equipment shall be provided in a new or good used condition:

- 4 computer work station desks
- 4 computer desk chairs
- 3 four-drawer legal size filing cabinets
- 1 conference table for 10-12 attendees (may also be a combination of folding tables)
- 12 conference chairs (may be padded folding)
- 2 drafting tables
- 2 drafting stools
- 1 plan holder rack with 12 plan sticks
- 1 Multi-function machine with color copier, multi-page scanner, and printer with network capability (Canon Aficio MP 3500 or approved equal), capacity to print and copy in duplex, color and staple.

<u>CATEGORY B: Computer Equipment & Software</u>

Two (2) each of the following computer equipment and software shall be provided new by the Contractor and upon completion of the project shall become the property of the City. The equipment and software shall be capable of providing work processing and utilizing all the software provided.

Core System Specification:
- Dell Precision T7500
- Quad Core Intel® Xeon® Processor X5550 2.66GHz,8M L3, 6.4GT/s,turbo
- 1.5GB NVIDIA® Quadro® FX 4800, DUAL MON, 2DP & 1DVI
- 250GB SATA 3.0Gb/s with NCQ and 8MB DataBurst Cache™
- 4GB, DDR3 Memory,1333MHz
- 16X DVD+/-RW

Monitor:
- Dell UltraSharp™ 2408WFP 24in HAS Wide Monitor, VGA/DVI

Installed Software
- Microsoft Windows 7 Professional
- Microsoft Office 2009 Professional
- Adobe Acrobat 9.0 Standard Ed.
- Adobe Photoshop Elements 8
- McAfee 10 Security Software
- Cyberlink PowerDVD™ and Roxio Creator™ Dell Ed
- Resource DVD - contains Diagnostics and Drivers

Accessories:
- Dell AX510 Sound Bar for all UltraSharp Flat Panel Displays
- New Dell USB Optical Mouse with scroll, All Black Design
- Dell QuietKey Keyboard

Project camera:
- Canon PowerShot SX20 IS
- eight (8) AA of 2700 mAh NiMH batteries with charger

O. The Contractor shall be responsible for the maintenance and corresponding supply of items for the above listed such as, printer cartridges, copier toner, copier maintenance, etc., as necessary.

P. The Engineer will exercise reasonable care in connection with security, but if the office trailer, or any of the office equipment is lost due to theft or fire, it shall be at the risk of the Contractor and shall be replaced by the Contractor at this own expense.

10. Reference: **SECTION 02232 AGGREGATE BASE**, Part 1.02 Measurement and Payment, Paragraph A, page 02232-1

Replace paragraph A with the following:

A. Aggregate Base in Roadway Section shall be measure and paid for by ton of materials placed in accordance to the contract documents.

11. Reference: **SECTION 02740 ASPHALTIC CONCRETE PAVEMENT**, Part 1.8 Measurement and Payment, Paragraph A, page 02740-2

Delete the first sentence of the paragraph:

A. ~~AC Pavement (6" AC/24" AB Cl II) will be measured and paid for per square foot as shown on the plans and in the Bid Sheet.~~

Replace the first sentence with the following:

A. Asphalt Concrete (AC) Pavement in Roadway Section shall be measured and paid for by ton of materials placed in accordance to the contract documents.

12. Reference: **SECTION 02740 ASPHALTIC CONCRETE PAVEMENT**, Part 1.8 Measurement and Payment, Paragraph B, page 02740-3

Delete Paragraph B.

13. Reference: **SECTION 02740 ASPHALTIC CONCRETE PAVEMENT**, Part 1.8 Measurement and Payment, Paragraph C, page 02740-3

Replace the paragraph with the following:

C. Grind AC Pavement will be measured and paid for per square foot in accordance to the contract documents. The unit price shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in grinding the ac pavement complete and in place.

14. Reference: **SECTION 14211 ELECTRIC TRACTION ELEVATORS,** Part 1.02 Design Requirements, Paragraph A, page 14211-1

Add the below mentioned item no. 2.

2. Coordination of basic elevator dimensions such as shaft clearances, pit depth and cab overrun shall be the responsibility of the General Contractor and the elevator manufacturer. All costs required for changes to the design, caused by an alternate manufacturer, including design and construction costs to building elements shall be included in the base bid and shall not considered additional charges to the contract.

15. Reference: **SECTION 14211 ELECTRIC TRACTION ELEVATORS**, Part 2.01 Manufacturer, page 14211-6

    Add the below mentioned paragraphs B and C.

    B. Alternate manufacturers that meet the contract specifications including materials quality, and performance criteria shall be considered as equal.

    C. Refer to Section 1.02 Design Requirements, paragraph A., item no. 2. for coordination and cost responsibilty between General contractor and for alternate elevator manufacturers.

PLANS: PACKAGE #1

16. Reference: **SHEET A2.1**, P2 Level Parking Plan

    Remove Note 7.

    7. ~~NOTE: ALL GRADES ARE RELATIVE TO ESTABLISHED DATUM 00.00 WHICH EQUALS 00.00 AS SHOWN ON CIVIL DRAWINGS~~

    And replace with the following:

    7. SPOT ELEVATIONS REFER TO ACTUAL DATUM ELEVATIONS.

ADDENDUM NO. 2:

17. Reference: **ITEM 8**

    Add the following to the VOLUME B TABLE OF CONTENTS.

    02780 Unit Pavers

    Both Sections 02780 Unit Pavers and 02785 Granite Pavers shall be maintained in the specifications.

If you have any questions regarding this addendum, please contact Gabriel Salinas, Senior Project Manager at (925) 291-3716 or Allan A. Panganiban, Senior Civil Engineer at (707) 648-4686.

Sincerely,

DAVID A. KLEINSCHMIDT
City Engineer

Attachment: Technical Specification Section 01220 Unit Prices

Acknowledgment of Receipt

_____
Bidder's Signature

_____
Date

THIS ADDENDUM NO. 3 MUST BE ATTACHED TO THE BID DOCUMENTS

cc: PW Chron. file

ATTACHMENT TO ADDENDUM #3

SECTION 01220
UNIT PRICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for unit prices.

1.3 DEFINITIONS

A. Unit price is an amount incorporated in the Agreement, applicable during the duration of the Work as a price per unit of measurement for materials, equipment, or services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification, if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.

1.4 PROCEDURES

A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.

B. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.

C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.

D. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

A. Unit Price No. 41 – Mobilization – Package #2:

1. Description: Delivery and setup of equipment in staging location according to Section 11 of the Caltrans Specifications.
2. Unit of Measurement and Payment: Lump sum.
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

B. Unit Price No. 42 – Traffic Control Package #2:

1. Description: Setup traffic control signage, flaggers and implementation according to Section 12 of the Caltrans Specifications.
2. Unit of Measurement: Lump sum.
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

C. Unit Price No. 43 – Clearing and Grubbing:

1. Description: Clearing and Grubbing as shown on the plans and according to Section 02100 “Site Preparations.”
2. Unit of Measurement: Lump sum.
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

D. Unit Price No. 44 – Remove Miscellaneous Items:

1. Description: Removal and disposal of various items shown on the plan incuding but not limited to curb, curb and gutter, bike lockers, signs and posts, guard rail, bollards, telephone booths, ac pavement without the underlying aggregate base, concrete pavement without the underlying aggregate base, sidewalk without the underlying aggregate base, curb ramp, driveway without the underlying aggregate base, flag poles, chain barriers, storm drain pipes and inlets, tree, bench, wheel stop, bus shelter, trash can, electric car charging stations, pull boxes, cabinets, and electrolier according to Section 02100 “Site Preparations.”
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

E. Unit Price No. 45 – Earthwork/Excavation:

1. Description: Earthwork including loading, hauling and disposing of excess material, removal of all existing materials within the roadway, parking lot prisms and median, excluding those materials specially covered under removal items, as required for construction of the bus duck-out, intersection bulb-out, sidewalk and median. Measurement shall be made from just below the surface material removed in Bid Item #44 to the top of the final subgrade as shown on the plans and according to Section 02200 "Earthwork."
2. Unit of Measurement: Cubic Yard.
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

F. Unit Price No. 46 – Asphalt Concrete (AC) Pavement in Roadway Section:

1. Description: Place AC Pavement as shown on the plans according to Section 02740 "Asphaltic Concrete Pavement." The unit paid for this item shall include all labor and materials necessary to furnish and install surface preparation, prime coat, and fog seal. The unit paid for this item shall also include all labor and materials to adjust the grade as necessary of existing manholes, valve boxes, and utility vaults within the area to be repaved or receive new pavement.
2. Unit of Measurement and Payment: Ton.
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

G. Unit Price No. 47 –Aggregate Base in Roadway Section:

1. Description: Place Aggregate Base as shown on the plans according to Section 02232 "Aggregate Base." The unit paid for this item shall include all labor and materials necessary to furnish and install aggregate base including sub-grade preparation and compaction. Aggregate Base in Roadway Section does not include aggregate base beneath the bus pad, hardscape, curb ramps, median hardscape, Type "A" curb, and curb and gutter.
2. Unit of Measurement and Payment: Ton
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

H. Unit Price No. 48 –Grind AC Pavement:

1. Description: Grind 2" asphaltic concrete paving as shown on the plans according to Section 42-2 of the Caltrans Standard Specfications.
2. Unit of Measurement and Payment: Square feet.
   Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

I. Unit Price No. 49 – Bus Pad (includes 9-inch PCC and 13-inch AB CL 2):

1. Description: Place Bus Pad as shown on the plans according to Section 02750 "Concrete Pavement." The unit paid for this item shall include all labor and

materials necessary to furnish and install concrete pavement, aggregate base, steel reinforcement, and rebar dowels. The unit paid for this item shall also include all labor and materials to adjust the grade as necessary of existing manholes, valve boxes, and utility vaults within the area to be receive concrete pavement.

2. Unit of Measurement and Payment: Square Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

J. Unit Price No. 50 – Hardscape (includes 4-inch PCC and 4-inch AB CL 2):

1. Description: Place Hardcape as shown on the plans according to Section 02750 “Concrete Pavement.” The unit paid for this item shall include all labor and materials necessary to furnish and install concrete pavement, finishing treatment per landscape plans, aggregate base, steel reinforcement, and rebar dowels. The unit paid for this item shall also include all labor and materials to adjust the grade as necessary of existing manholes, valve boxes, and utility vaults within the area to be receive concrete pavement.
2. Unit of Measurement and Payment: Square Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

K. Unit Price No. 51 – Median Hardscape:

1. Description: Place Median Hardcape as shown on the plans according to Section 02750 “Concrete Pavement.” The unit paid for this item shall include all labor and materials necessary to furnish and install concrete pavement, finishing treatment per landscape plans, aggregate base, steel reinforcement, and rebar dowels. The unit paid for this item shall also include all labor and materials to adjust the grade as necessary of existing manholes, valve boxes, and utility vaults within the area to be receive concrete pavement.
2. Unit of Measurement and Payment: Square Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

L. Unit Price No. 52 – Curb Ramp:

1. Description: Place Curb Ramp as shown on the plans according to Section 02750 “Concrete Pavement.” The unit paid for this item shall include all labor and materials necessary to furnish and install concrete pavement, finishing treatment per landscape plans, aggregate base, detectable warning surface, steel reinforcement, and rebar dowels. The unit paid for this item shall also include all labor and materials to adjust the grade as necessary of existing manholes, valve boxes, and utility vaults within the area to be receive concrete pavement.
2. Unit of Measurement and Payment: Each
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

M. Unit Price No. 53 – Type ‘A’ Curb:

1. Description: Place Type ‘A’ Curb as shown on the plans according to Section 02750 “Concrete Pavement.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Type ‘A’ Curb including surface preparation, concrete, steel reinforcement, and Class 2 Aggregate Base.
2. Unit of Measurement and Payment: Linear Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

N. Unit Price No. 54 –Curb and Gutter:

1. Description: Place Curb and Gutter as shown on the plans according to Section 02750 “Concrete Pavement.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Curb and Gutter including surface preparation, concrete, steel reinforcement, and Class 2 Aggregate Base.
2. Unit of Measurement and Payment: Linear Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

O. Unit Price No. 55 – Lane Markings, Crosswalks and Directional Arrows:

1. Description: Place Lane Markings, Crosswalks and Directional Arrows as shown on the plans according to Section 02764 “Roadway Pavement Markings.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Lane Markings, Crosswalks and Directional Arrows including surface preparation.
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

P. Unit Price No. 56 – Package #2 Irrigation System:

1. Description: Furnish and install Package #2 Irrigation System as shown on the plans according to Section 02810 “Irrigation.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Irrigation System.
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

Q. Unit Price No. 57 – Package #2 Planting:

1. Description: Furnish and install Package #2 Planting as shown on the plans according to Section 02900 “Planting.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Planting.
2. Unit of Measurement and Payment: Lump Sum

3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

R. Unit Price No. 58 – Package #2 Site Furnishings:

1. Description: Furnish and install Package #2 Site Furnishings as shown on the plans according to Section 02870 “Site Furniture.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Site Furnishings
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

S. Unit Price No. 59 – 15” RCP:

1. Description: Place 15” RCP Class III Storm Drain as shown on the plans according to Section 02420 “Storm Drainage System.” The unit paid for this item shall include all labor and materials necessary to furnish and install the storm drain pipe including all trenching and backfill.
2. Unit of Measurement and Payment: Linear Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

T. Unit Price No. 60 – 24” RCP:

1. Description: Place 24” RCP Class III Storm Drain as shown on the plans according to Section 02420 “Storm Drainage System.” The unit paid for this item shall include all labor and materials necessary to furnish and install the storm drain pipe including all trenching and backfill.
2. Unit of Measurement and Payment: Linear Feet
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

U. Unit Price No. 61 – Convert Storm Drain Inlet to Manhole:

1. Description: Replace Storm Drain Inlet with a Manhole as shown on the plans according to Section 02420 “Storm Drainage System.” The unit paid for this item shall include all labor and materials necessary to remove the existing DI and furnish and install the Manhole.
2. Unit of Measurement and Payment: Each
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

V. Unit Price No. 62 –Storm Drain Inlet Type B:

1. Description: Place Type B Storm Drain Inlet as shown on the plans according to Section 02420 “Storm Drainage System.” The unit paid for this item shall include all labor and materials necessary to furnish and install the DI.
2. Unit of Measurement and Payment: Each
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

W. Unit Price No. 63 –Storm Drain Inlet Type D:

1. Description: Place Type D Storm Drain Inlet as shown on the plans according to Section 02420 “Storm Drainage System.” The unit paid for this item shall include all labor and materials necessary to furnish and install the DI.
2. Unit of Measurement and Payment: Each
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

X. Unit Price No. 64 –Storm Drain Manhole:

1. Description: Place Storm Drain Manhole as shown on the plans according to Section 02420 “Storm Drainage System.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Manhole.
2. Unit of Measurement and Payment: Each
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

Y. Unit Price No. 65 – Package #2 Street Lighting System:

1. Description: Furnish and install Package #2 Street Lighting System as shown on the plans according to Division 16 “Electrical.” The unit paid for this item shall include all labor and materials necessary to furnish and install the Street Lighting System.
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

Z. Unit Price No. 66 – Modify Traffic Signal (Mare Island/Maine):

1. Description: Modify the traffic signal at Mare Island Way and Maine Street as shown on the plans according to Section 02453 “Traffic Signal.” The unit paid for this item shall include all labor and materials necessary to modify the Traffic Signal.
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

AA. Unit Price No. 67 – Modify Traffic Signal (Mare Island/Georgia):

1. Description: Modify the traffic signal at Mare Island Way and Georgia Street as shown on the plans according to Section 02453 “Traffic Signal.” The unit paid for this item shall include all labor and materials necessary to modify the Traffic Signal.
2. Unit of Measurement and Payment: Lump Sum
3. Quantity Allowance: Coordinate unit price with allowance adjustment requirements in Division 01 Section "Allowances."

END OF SECTION 01220